

#### ADDENDUM #1

# <u>City of Duluth</u> <u>Fire Station #10 Slab replacement</u>

Project #: 13-032TR Bid #: 13-25DS

The following addendum shall become part of the construction documents for the construction of the above referenced project. This addendum supersedes and supplements all previous reference to similar items.

### CITY OF DULUTH PROJECT REQUIREMENTS

Add the following:

Sheet S1.0 Structural Notes

### Design Criteria, Loads and Stresses

A. Concrete

Add Line 8:

Silica fumed concrete shall be 5% replacement of portland cement in the concrete mix design.

## Silica Fumed Bonded Concrete Overlay: Work Item#3

Line #1 should read:

Saw cut and remove existing un-bonded concrete topping slab to the extent shown on plans

**END OF ADDENDUM #1**