

ADDENDUM NO. 2

To The Plans and Specifications for

Roof Replacement Four (4) Bldgs

Animal Shelter-C; Fire Hall #4-A; Fire Hall #7-B; Fire Hall#10-D
Duluth, Minnesota 55779

Prepared By:

Scalzo Architects Ltd
1901 South Street
Duluth, Minnesota 55812

Northland Consulting Engineers LLP
102 South 21st Avenue West
Duluth, Minnesota 55806

May 1, 2015

This Addendum includes revisions, additions and changes to the Contract Documents for the above referenced project and shall become part of the project Contract Documents.

Bidders are requested to include the items listed in this addendum as part of their Bid.

Attached hereto are the following drawings: None

Changes to Drawings

Sheet A3.0

1. Specifications. 10. Add the following sentence. City of Duluth to provide testing for materials suspected to contain hazardous materials prior to commencement of the Work.
2. Specifications. 15. Revise to read " including 55 MPH wind speed coverage." In lieu of "with extended wind up lift coverage: wind speed 90 mph."

Animal Shelter

Sheet A3.0

3. Specifications. 20. Add the following: Mechanically fasten glass mat roof board to metal deck.
4. Specifications. 22. Delete in its entirety.

Fire Hall 4

Sheet A2.0

5. The existing upper ballasted roof is assumed to contain asbestos materials; Contractor bid to include removal and disposal of asbestos materials. City of Duluth to provide testing prior to the commencement of the Work.

Fire Hall #7

Sheet A3.0

6. Specifications. 22. Delete in its entirety.
7. Specifications. 24. Delete in its entirety.

End of Addendum